

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**

**CIN No.U40109MH2005SGC153646**

<b>Name of Office :- EHV Project Division, MSETCL, Nanded.</b>	
<b>Office Address :- Office of the Executive Engineer, 12 kV Jangamwadi Substation Campues, Nanded-431605</b>	
<b>Contact No. :- Tel. 263105 (O) 260107 (P) 261981</b>	<b>Fax No. :- 264107</b>
<b>Email :- <a href="mailto:ee260@mahatransco.in">ee260@mahatransco.in</a>;</b>	<b>Website :- <a href="http://www.mahatransco.in">www.mahatransco.in</a></b>
<b>Ref. No. EE/EHV/Proj/Div./Nanded/TS/1181</b>	<b>Date:-28.09.2022</b>

**E-Enquiry**

**Subject:-** E-Enquiry for the work of detail Survey of 132 kV SCDC Gunj-Mahur Line under EHV Projects Division Nanded.

Dear Sir,

Sealed & super scribed quotation are invited from date **29.09.2022**, so as to reach this office up to date **05.09.2022 up to 17:00 hrs** for work of detail Survey of 132 kV SCDC Gunj-Mahur Line under EHV Projects Division Nanded on following terms & conditions:-

**TERMS AND CONDITIONS:-**

1. The rate shall be quoted on firm quotation basis.
2. The rates should be quoted excluding / including of taxes. The taxes if any should be quoted extra.
3. The quotation should be sent under sealed cover duly super scribed as QUOTATION FOR work of detail Survey of 132 kV SCDC Gunj-Mahur Line under EHV Projects Division Nanded.  
(Enquiry No. \_\_\_\_ be quoted).
4. Your quotation should reach this office **on or before 05.09.2022 up to 17:00 hrs** and the same will be opened on the same day, if possible.
5. The rates shall be quoted **excluding** or **including GST** in **rate column of schedule**. The rates and amount shall be written both in words and figures. The rates shall be written legibly and shall be free from eraser. The rates quoted shall include all the machineries, T&P and personnel required for executing the works.
6. You will have to pay the security deposit of 5% of the order value within Seven (7) days from the date of receipt of firm order. Security Deposit is payable by (a) Cash (b) D.D. (c) F.D.R / Bank Guarantee from a nationalized scheduled Bank in the name of Executive Engineer EHV Project Division Nanded. The S.D. will be refunded after satisfactory completion of the work subject to NOC from concern officer.
7. Income tax will be recovered as per prevailing rules.
8. The rates offer submitted by you should be valid for at least 90 days from the last date of receipt of quotation.

9. Payment will be effected by this office by cheque or RTGS after satisfactory completion of work.
10. The work shall be under the supervision of the Addl. Executive Engineer, S&I S/Dn. Nanded or his representative.
11. Please quote your PAN, GST No. on the quotation.
12. The documents required:- The rate offer must be accompanied with following valid documents duly attested & signed by agency.
  - a) Copy of valid Civil contractor license,
  - b) Valid Shop Act License.
  - c) PAN Card.
  - d) GST Registration.
  - e) Valid WC policy.
  - f) Experience certificate of similar type of work executed in MSETCL (not below the rank of Executive Engineer)
13. The T&P for the work will be arranged by the agency.
14. The persons engaged by you must be well trained for above work.
15. The undersigned reserves the right to place order either partly or fully or to reject any or all the quotations without assigning any reasons whatsoever.
16. All the MSETCL's general terms & conditions for purchase will be binding on you.
17. Before quoting rates, agency if needed may inspect the site.

Thanking you.

S/d  
(S N Nalbalwar)  
**Executive Engineer (I/C)**  
**EHV Project Division, Nanded**

**Copy SWRT:-**

1. The Chief Engineer, EHV P.C. O&M Zone Aurangabad
2. The Superintending Engineer, EHV Project Circle Aurangabad

**Copy to:-**

1. The Addl.EE, S&I, S/D, Nanded
2. The Mgr (F&A), EHV Project Division, Nanded.
- Website:- [www.mahatransco.co.in](http://www.mahatransco.co.in) / Notice Board.

**Schedule:-** Detail Survey of 132 kV SCDC Gunj-Mahur Line under EHV Projects Division Nanded.

Sr. No.	Particulars	Unit	Qty.	Rate / Unit is to be quoted in Rs.	Amount
1	Preliminary survey with GPS Survey, Theodolite, Marking route on Topo Sheets representing actual field condition etc. complete in all respect.	KM	20		
2	Detail survey including tower spotting and tower profiles detailed survey with GPS Total station, Digital Theodolite etc. along the approved alignment, preparation of profiles, tower spotting, tower schedules and soil resistivity, making of route on Topo Sheet and village map etc.	KM	20		
3	Excavation of trial pits of standard dimension of 1 mtr x 1 mtr width upto 3 mtrs depth at 1 KM interval or where ever there is abnormal change in topography and taking observation of soil strata for classification of foundation and backfilling the trial after visiting by Departmental officials	Per Pit	20		
	<b>Total Amount</b>				
	<b>Taxes if any then quote separately :-</b>				

Note:-

1. Estimated amount in **Rs. 6,41,719/-** inclusive of all taxes.
2. Please mention **GST @ .....****Extra or Including in Taxes.** Otherwise rates will be presumed as inclusive of GST)
3. Final Total amount for lowest amongst all agencies will be compared irrespective of individual item rates.

**Signature & Seal of Agency**