

## **Maharashtra State Electricity Transmission Co. Ltd.**

Office of The Executive Engineer, EHV Project Division,  
In the premises of 132KV MIDC Substation, Plot No.21, Barshi Road, Latur-413512.  
Ph. 02382-222990, Fax 02382-221990.  
Email Id :-ee2620@mahatransco.in

EE/EHV/PROJ/LTR/Tech/ 1697

Dt. 29.09.2022

### **e-Enquiry For Work**

**Name of Work:** - Work of preliminary & detail survey as & when required for various projects under jurisdiction of EHV Project Division, Latur.

Sir,

Sealed quotations are invited from the reputed, experienced / Registered contractor in separate envelope duly superscribed with the above subject, so as to reach this office on or before **06.10.2022 upto 16.00 Hours** for the above said work subject to the terms and conditions detailed below -

#### **TERMS AND CONDITIONS**

15. Scope of Work : The survey should be carried out in accordance with the particulars and description of items enlisted in the Schedule 'A'. The other details if required, are available in this office.
16. You are requested to quote your reasonable rates in the format mentioned in annexure 'A'. It must include cost of materials, labour charges and T&P etc. required for execution of the work.
17. All the equipments/survey material instruments required for survey, T&P, vehicles, etc. and labours shall be arranged by you. No T&P or labour or equipments will be given by the MSETCL.
18. The contractor should have experience of similar type of work 30 Km.
19. If any damage is occurred to the contractor's equipment/T&P OR any accident to your labours/personnel, the M.S.Elec. Trans. Co. Ltd. will not be responsible in any way. Also if any theft/loss of material is occurred, the M.S. Elec. Trans. Co. Ltd. will not be responsible in any way.
20. According to finance Act 194 (c) of 1972 an Income Tax as applicable will be deducted from your bill.
21. The work should be completed within **60 working days** from the date of handing over of work site, failure of which a penalty equal to 1% per week subject to the maximum of 5% of the ordered value will be levied.
22. The work should be strictly carried out as per standard specifications and upto the entire satisfaction of the Engineer-in-charge.
23. The contractor will have to pay security deposit to the M.S. Elec. Trans. Co. Ltd. equal to 5% of the ordered value.
24. All the documents should have authorized signature from the bidder.
25. The terms and conditions enumerated in the M.S.Elec. Trans. Co. Ltd.'s booklet "Tender and Contract for Works" will be applicable in this case and will be binding on the contractor entirely.
26. Right to accept any or to reject any or all the quotations without assigning any reasons thereto is reserved.
27. The quantities enumerated in attached Schedule 'A' are approximate and payment will be made against actual executed quantities.

28. Whenever "MSEB" appears should be read as M.S. Elect. Trans. Co. Ltd. and offer should be submitted to M.S. Elect. Trans. Co. Ltd. instead of MSEB as per directives.


Check List for Documents :-

- 6) Experience Certificate
- 7) Shop Act Licence
- 8) Labour Licence
- 9) GST certificate
- 10) PAN Card

Thanking you,

Encl:- Schedule 'A', Annexure A

Yours faithfully

  
Executive Engineer  
EHV Proj. Dn. MSETCL  
Latur.

Copy S.W.R.S. to-

- 2) The Superintending Engineer, EHV Project Circle, Aurangabad.


Copy to:-

- 3) The Addl. Executive Engineer, EHV S&I S/Dn, Latur.
- 4) The Manager (F&A), EHV Proj. Division, Latur.

### SCHEDULE 'A'

**Name of Work :-** Work of preliminary & detail survey as & when required for various projects under jurisdiction of EHV Project Division, Latur.

Sr. No.	Particulars of Item	Unit	Rate
1	2	3	4
1	Preliminary survey with GPS Survey, Theodolite, Marking route on Topo Sheets (3 sets) representing actual field condition etc. complete in all respect.	KM	
2	Detailed Survey with Total station/ Theodolite /DGPS etc. Including tower spotting and Schedules preparation of tower profiles, approval of alignment, making of route/corridor on topo sheet, Village map & Khasra map, Identification of forest, railway crossing, Highway crossing, proposed development along the route/corridor etc. Collection of 7/12 along the route/corridor.	KM	
3	Providing & fixing dressed header stone pillars of size 150x100x650mm for tower line centre reference pillars and fixing in centre line, an embedding in cement concrete 1:3:6 mix of 500x500x750 size block, including painting of exposed portion by oil paint and centre line point marked over pillars embedded. pillars will be provided at every angle point with guide pillars in both direction & at road crossings, at average 2 to 3 numbers per Km or as directed by engineer incharge wherever necessary.	Per no.	
4	Excavation of trial pits of standard dimension of 1 mtr x 1 mtr width upto 3 mtrs depth/ up to hard rock at 1 KM interval or where ever there is abnormal change in topography and taking observation of soil strata for classification of foundation and backfilling the trial after visiting by Departmental officials and submission of trial pits report.	Per pit	

  
Executive Engineer  
EHV Proj. Dn. MSETCL  
Latur.