

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.
INTRA OFFICE COMMUNICATION

Name of Office	: Executive Engineer, EHV Projects Division, Kolhapur
Office address	: Vidyut Bhavan, Admm. Building, 2nd Floor, Tarabai Park, Kolhapur.
Contact No.	: 0231- 2665320 (P), 0231- 2655937 (O)
E-Mail	: ee3610@mahatransco.in

Ref. : EE/EHV Projects/Dn./Kop/E-Enquiry/No. 2024

Date : 28.11.2022

Sub : E-Enquiry for the supply & Erection work in respect of shifting of 11 KV & LT Line under MSEDCL O&M Division, Jaysingpur.

Dear Sir,

The sealed & subscribed quotations are invited for supply & Erection work in respect of shifting of 11 KV & LT Line under MSEDCL O&M Division, Jaysingpur as per the Schedule 'A' attached herewith subject to following terms & conditions.


TERMS AND CONDITIONS :

- 1) The quotations should reach to this office on or before **05.12.2022 upto 16.00 Hrs.** This office shall not accept any responsibility for late receipt of quotations due to postal delay.
- 2) The contractor has to furnish GST, PAN No. in the offer.
- 3) The following documents shall be submitted with the offer,
 - a. Valid copy of Electrical contractors license issued by Govt. of Maharashtra.
 - b. Registration under works contract Act.
 - c. Insurance copy of your working employees/Labour.
- 4) The rates quoted by the bidder, shall be considered as inclusive of GST & all other duties, taxes other levies LBW Cess, IT etc. which are payable by the contractor as per statutory regulations.
- 5) Income tax & Labour welfare cess shall be deducted from the bills at prevailing rates, as per Income Tax Act 1961, GST TDS @ 2% will be deduct from your bill.
- 6) Bids shall remain valid for 90 days after the date of bid opening prescribed by the employer.
- 7) **The estimated amount of said work is Rs. 4,59,520/- incl. supervision charges.**
- 8) The work is to be executed under supervision of MSEDCL.
- 9) Security Deposit
Within Fifteen (15) days of the receipt of notification of award i.e. the letter of intent from the Employer, the successful bidder shall furnish the security deposit amounting to 5% of the contract value by cash/ cheque/DD.
- 10) Period : The time period for completion of the item under Schedule 'A' under this contract will be 1 Month. The period shall be entitled from date of handing over of the site.
- 11) If the work is not completed within stipulated period, the liquidated damages shall be levied at ½% (half percent) of the total contract price per week of delay subject to maximum of 10% (Ten percent) of the contract price for the entire scope of work.

- 12) Payment will be made at Division Office, Kolhapur after completion of 100% work carried out by the contractor for all approved works executed as fixed by the Engineer after proper measurements and scrutiny of bills at concerned Sub-Division Office.
- 13) The contractor has to execute the agreement on stamp paper as per Govt. rule, before commencement of work.
- 14) All T & P, Labour, Crane etc. shall be arranged by the contractor at his own cost.
- 15) The contractor shall make his own arrangements for the engagement of all labour local or otherwise and shall make his own arrangement for their accommodation & transportation. Permission will not be granted to stay at site.
- 16) The contractor shall not sub-let the works awarded on him under this contract.
- 17) The tenderer shall arrange for posting his own security personnel at his own cost to safeguard the material handed over to him not only at his storage yard but also at the work site till such time the complete job is ultimately handed over to Maharashtra State Electricity Transmission Company Ltd.
- 18) Guarantee - The work executed under this contract shall be guaranteed for 12 months from the date of completion of work.
- 19) The bidder is advised to visit and examine the Site of Work and its surrounding and obtain for himself, on his own responsibility, all information that may be necessary for preparing the bid and entering into the Contract. The cost of visiting the Site shall be a bidder's own expense.
- 20) Quotation incomplete in any respect shall be rejected.
- 21) Executive Engineer reserves the right to reject any or all the quotations without assigning any reason therefore.
- 22) Quotation received late or with incomplete details against above clauses will not be considered.
- 23) Labour welfare cess/GST/other statutory payment etc. considered in contract value will be deducted at appropriate rate prevailing during tenure of contract.

Thanking You.

Yours faithfully,



(A.S. Kulkarni)
Executive Engineer,
EHV Projects Dn. Kolhapur.

Encl. : Schedule A.

Copy s.w.rs. to :

The Suptd. Engineer, EHV Projects Circle, Kolhapur.

Copy to :

- 1) The Addl. Executive Engineer, EHV Line Projects S/Dn.-II, Kolhapur.
- 2) The Manager (F&A) EHV Projects Dn. Kolhapur.
- 3) Notice Board.
- 4) MSETCL, Website.
- 5)

M/F.

EHV PROJECTS DIVISION, KOLHAPUR

“ SCHEDULE – A ”

Name of Work : Supply & Erection work in respect of shifting of 11 KV & LT Line under
MSEDCL O&M Division, Jaysingpur

Sr. No.	Description of work	Unit	Quantity	Quoted Amount In Rs. Incl. GST & Supervision Charges
A	Shifting of 11 KV Pingara feeder at Sambhajipur, Tq. Shirol & LT Line at Laman Vasahat, Jaysingpur, Tq. Shirol under.	No.	LS (Details as per Annexure – A-1 & A-2)	
Total :				

- Note :**
- (1) The aforesaid works are inclusive of Supply, Erection, Civil foundations, painting, dismantling & all allied works required for completion of the work.
 - (2) Amount shall be quoted inclusive of supervision charges.
 - (3) All the required T&P shall be arranged by the contractor.
 - (4) The work shall be executed strictly as per the norms of MSEDCL.
 - (5) The rates shall be quoted in line with the MSEDCL Cost Data.

Signature of Contractor


**Executive Engineer,
EHV Projects Dn. Kolhapur.**

Date:

EHV PROJECTS DIVISION, KOLHAPUR

“ANNEXURE – A1”

Name of Work : Supply & Erection work in respect of shifting of 11 KV & LT Line under
MSEDCL O&M Division, Jaysingpur

Sr. No.	Description of Materials Required	Unit	Quantity
1	RSJ Poles of 11 Rmt 100 X 116 MM	No.	1
2	H.T. Stay Set	Set	2
3	H.T. Stay Wier 7/4 mm (8SWG)	Kg.	20
4	HT Stay Clamp	Pr.	2
5	11 KV V-X arm with clamp	No.	1
6	11 Top fitting with clamp	No.	1
7	11 KV Pin Insulators with G.I. pins	No.	3
8	11 KV Single pole cut point channel	Pr.	1
9	3- Hole strips	Pr.	3
10	a) 11 KV Hardware set complete (Weasel)	Set	6
11	Strain Hardware for Dog. 0.1 or Equ. AAAC	Set	6
12	G.I. Wire 8 SWG	Kg.	15
13	MS Nut Bolts	Kg.	20
14	Concreting of stays & Poles (1:4:8)	Cmt.	1
15	11 KV Danger board	No.	1
16	H.T.Earthing Set	Set	1
17	Painting of poles (Red, Alu & Black) by 2 coats of Red oxide & 1 coat of Al. paint	Per po	1
18	Sundries	LS	1
19	G.I.Barbed Wire 'A' type	Kg.	5
20	Disc insulator 11 KV 4500 KG	No.	3
21	LT Line	Km.	0.06

EHV PROJECTS DIVISION, KOLHAPUR

“ANNEXURE – A2”

Name of Work : Supply & Erection work in respect of shifting of 11 KV & LT Line under
MSEDCL O&M Division, Jaysingpur

Sr. No.	Description of Materials Required	Unit	Quantity
1	XLPE Cable 11 KV , 3 C / 300 mm sq.	Rmt.	200
2	R.C.C. Pipe 150 mm 2 M	No.	20
3	Half round cement pipe (150 mm. X 1 mtr.)	No.	120
4	11 KV heat shrinkable Outdoor termination joint kit for 3C X 300 sqmm.	No.	4
5	Sand	Cmt.	250