

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

CIN No.U40109MH2005SGC153646

Name of Office :-	EHV (O&M) DIVISION, NANDED.
Office Address :-	132 KV S/S JANGAMWADI, CAMPUS, MSETCL NANDED- 431605
Contact No. :-	02462 – 261817 (O), 02462 – 261817 (Fax) 02462 – 261816 (P)
Email :-	ee2240@mahatransco.in ; eenanded@gmail.com
Ref. No. EE/EHV(O&M)/NND/TS/ File No.73/	No 150 - Date :- 20 FEB 2023

E-Enquiry

To,

Subject:- E-Enquiry for work of concreting of foundation of 01 nos. leg including stub strengthening of adjacent leg of 132kV Umri Kundalwadi line under EHV O&M Division, Nanded.

Dear Sir,

Sealed & super scribed quotation are invited from date **20.02.2023**, so as to reach this office up to date **26.02.2023 up to 17:30 hrs** for work of concreting of foundation of 01 nos. leg including stub strengthening of adjacent leg of 132kV Umri Kundalwadi line under EHV O&M Division, Nanded on following terms & conditions:-

TERMS AND CONDITIONS:-

- 1) Please refer the schedule attached herewith and quote your offer for the same.
- 2) No Price variation is applicable. GST rate as applicable will have to be quoted separately in space provided. If nothing is specified rates will be considered as inclusive of all taxes.
- 3) **Documents required:** - the rate offer must be accompanied with the following documents duly attested & signed by the vendor.
 - a. Valid Electrical Contractor License.
 - b. Valid Goods & Service Tax (GST) registration certificate.
 - c. Valid Shop Act / MSME/ NSIC Registration.
 - d. PAN Card Copy.
 - e. Valid Workman compensation policy

4) SCOPE OF WORK:

- a. As per Schedule.
- 5) The contractor shall be fully responsible for compliance of all statutory obligations under the Factory Act 1948, Contract Labour (Regulation and Abolition) Act 1970, Maharashtra Labour Contract Regulation & Abolition Act, 1971, Minimum Wages Act, Provident Fund Act and ESIC Act / Workman Compensation Act 1926, Payment of Wages Act in respect of the Staffs deployed. The rules and regulation of the Contract Labour Act shall be binding on the contractor.

- 6) a. The Owner will not be responsible for violation of these statutory rules and regulations by the contractor.
- b. It shall be the sole responsibility of the contractor to observe all the relevant acts and regulations along with amendments thereto framed by the Government from time to time. The Owner shall not be responsible for violation of any of the above stated regulations / Acts etc. by the contractor.
- c. The work should be carried out strictly within 45 days from the handing over the site.
- d. The work carried out should be as per the standard practices of MSETCL.

7) You will have to arrange all tools, plants, skilled manpower etc. to carry out the work at your own cost.

8) You will have to provide all safety measures to your staffs while executing the work.

9) **GUARANTEE:-** You should give guarantee of the work done against this work order must be guaranteed for best performance at least for Two year from the date of work done.

10) The payment shall be made only after satisfactory completion of work as certified by the concern Engineer In-charge and as per availability of funds.

11) SECURITY DEPOSIT:

a. The successful Contractor(s) will have to submit Security Deposit at the rate of 5 % of the value of the order, by cash / Demand Draft / Fixed Deposit / Bank Guarantee at the office of the Executive Engineer, EHV O&M Division Nanded, within 07 (Seven) days from the date of receipt of letter of intimation.

b. The Demand Draft / Fixed Deposit / Bank Guarantee submitted towards the Security Deposit shall be in the name of the Executive Engineer, EHV O&M Division, Nanded.

c. If the successful Contractor fails to submit Security Deposit within the stipulated period, it will be presumed that the Contractor is not interested in execution of the contract and the work contract will be issued to other agency (i.e.). The decision of E-enquiry accepting authority i.e. the Executive Engineer, EHV O&M Division, Nanded shall be final and remain binding on the Contractor(s).

d. No interest will be paid on the Security Deposit and the Security Deposit will be refunded after satisfactory execution of works / guarantee period, whichever is later.

12) AGREEMENT & STAMP DUTY:-

a. The successful Contractor has to execute an Agreement with The Executive Engineer, EHV O&M Division, MSETCL; NANDED within 7 days after receipt of the work order.

b. The successful Contractor shall submit an Agreement Bond on non-judicial stamp paper as per the Clause 63 of Mumbai Stamp Duty Act 1958. The expenses towards the stamp paper and preparation of Agreement Bond will be on the part of the contractor.

13) The undersigned reserves the right to reject any or all the bids without assigning any reason whatsoever.

14) If the work is not carried out within the stipulated time / period, penalty @ ½% per week of the balance works will be recovered from the contractor's bill subject to 10% maximum.

15) Quantities Shown in Schedule are tentative and will be required as per site condition as per actual.

16) The Owner will not be responsible for any fatal or non fatal accident to the personnel of the agency. If any type of misconduct or adverse report against the performance of the personnel of the contractor is reported to this office, the undersigned reserves rights to cancel the contract at any stage. The decision of the undersigned in this regard will be final and binding on the agency.

17) **LIABILITY OF ACCIDENT / LOSS:** The contractor will be responsible for any accident to any of his personnel or loss to him during the work. The responsibility of the insurance towards the same shall be with the contractor. The compensation to the contractor's personnel will be the responsibility of the contractor.

18) **EXCEEDING THE CONTRACT VALUE:** The contractor will have to watch and ensure that the total value of work carried out by him does not exceed the contract value. If the work / value of contract is likely to be exceeded the same should be brought to the notice of the undersigned in writing. If the value of the total work exceeds the order value in that case the contractor is not permitted to execute the work without prior permission from the undersigned.

19) **DAMAGE TO PERSONS AND PROPERTY:** - Contractor will indemnify the MSETCL against any losses and claims regarding any injuries or damage to any person, material or physically damage any property whatsoever which may arise out of or in consequence of the execution of work. During execution of work any damage/loss to Transmission Company's property occurs will be recovered from your bill.

20) SUBLETTING OF THE CONTRACT:

- a. The contractor will not sublet / transfer / assign the contract as a whole or any part or any operation thereof to any other party.
- b. In case the contractor sublets/ transfers / assigns the contract as a whole or any part it or any operation thereof to any other party, it will be treated as breach of contract and the contract will be terminated at contractor's risk and cost.

21) INSURANCE:

- a. The contractor will arrange Employee State Insurance (ESI) for the Staffs employed or insurance policy
- b. The Workman Compensation Insurance of shall be on the part of the contractor.

22) **VALIDITY OF ORDER:** The order will be valid for until exhausting of the order amount OR for a period of six months from the date of issue of work order whichever is earlier.

23) GST, Income Tax, labour cess & statutory taxes as applicable shall be paid/deducted from your bills as per prevailing Government rules.

24) CONTRACTOR'S DEFAULT:

- a. In case you fail to complete work fully OR partially, the security deposit will be revoked by MSETCL. In this case the balance work will be got done from other agency may be at higher rates and the difference in cost will be recovered from the contractor's bills.
- b. In case of any loss / damage to the Owner's asset /material, it will be the sole responsibility of the contractor to lodge the complaint in writing to the nearest police station under intimation to this office or to In-charge/ designated officer.
- c. If there happens any loss of goods or damage to valuable material in the premises on account of negligence of the Staff, the cost of loss / damage shall be recovered from the contractor.

25) SUSPENSION / HOLDING OF WORK: If the work has to be suspended due to any reason i.e. stay order from court of law, legal held up from any other Agency, shut down etc. the MSETCL shall not pay any compensation / damage to the contractor towards item like idle labour, etc. In such cases the contractor is not liable for claiming extra payment.

26) DEDUCTION: Any Amount which become payable by the contractor to the MSETCL under particular contract will be deducted by the Owner from any amount due or becoming due to him to the contract under the same or any other contract.

27) SAVE AND EXCEPT: Amount due to account of damage or compensation for default or breach of contract by the contractor in which case instead of deduction of the same amount shall be retained and the Owner shall have the right on amount so retained or withheld.

28) TERMINATION OF CONTRACT: The Undersigned reserve the right to terminate the contract at any stage without assigning any reasons thereof.

29) GENERAL: The Contractor are also deemed to be fully aware of the company's general conditions of contract for work, supply of equipment/material and any ignorance of any of the condition will not exempt you from liability to abide by the same.

30) Validity period of quotation should be 90 days.

31) If any loss occurs to Company's property during execution of work, you should make it good at your own cost.

32) JURISDICTION: All disputes or difference arising out of and in connection with the contract shall be subject to the exclusive jurisdiction of Nanded Court only.

Thanking You.

Yours faithfully,



(M.G.Sonkamble)
Executive Engineer
EHV(O&M) Division Nanded.

Encl.:- "Schedule"

Copy SWRT:-

The Superintending Engineer, EHV O&M Circle Parli V

Copy to:-

1. The Dy. Manager (F&A), EHV O&M Division Nanded.
2. Website:- www.mahatransco.co.in

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

CIN No.U40109MH2005SGC153646


Schedule:- Work of concreting of foundation of 01 nos. leg including stub strengthening of adjacent leg of 132kV Umri Kundalwadi line under EHV O&M Division, Nanded.

Sr. No.	Particulars of Works	Unit	Tentative Qty.	Quote Rate per unit including 1% LC
1	Mobilization & Demobilization of T&P, Labours to the Site Location.	Per Occasion	1	
2	Excavation of pits for tower footings in earth soil of all types, sand gravel and normal soil including removing of excavated material beyond tower locations upto 50 M lead and all lifts, shoring, shuttering, preparing the bed for foundations and necessary back filling ramming after stub setting, compacting, finishing and curing complete in all respect as per drawing & direction of Engr. In- charge.			
A	Soft rock/Hrad Murum	CuM	0.3	
B	Dry Fissured Rock	CuM	1.0	
C	Hard rock by Chiseling	CuM	1.2	
3	Concreting of foundation: Providing and casting in situ cement concrete of trap metal of size 20 to 40 mm as applicable including cost of cement, sand, metal and water, frame work, finishing, compacting, coping and curing for 21 days complete as per drawing and direction of Engr.In-charge in the following grades-			
A	M 20 (1:1.5:3) with graded metal for foundation	CuM	1.26	
4	Providing and fixing in position Steel Reinforcement in concrete foundation including supply of TMT bars with epoxy coating/Meta cam of various diameters for R.C.C. work like raft, footing of column etc. as per drawing and direction which will be furnished by the owner including cutting, bending, hooking the bars, binding with binding wire or tackwelding etc. complete as directed.(Steel to be provided by contractor)	MT	0.027	
5	132 KV DC Tower : Stub setting in all type of soils with the help of Stub template /PROP setting including transportation if required to the desired location, fixing the stubs in position as per the alignment, Jacking, fixing and leveling the templete and the stub as directed by Engr.In-charge.			
A	2 Degree	Per Loc.	1	
6	<u>Stub Strenghtening Work involved</u> Excavation / Breaking of Existing foundation around the Tower Leg Breaking the Cement Concrete of Chimney upto the affected, corroded portion of stub. Cleaning the surface preparation of tower stubs. ii) Drilling of suitable size GI angles for inner side & outer side sections. iii) Painting the pieces / tower members upto 3 mtrs. Section and stub on either side with epoxy polymino amide base resin iv) Drilling the angle pieces to the stub. (Directed as per Mentioned in E-Enquiry or Engineer - In Charge)			
A	Suspension Towers (132KV Line)	Per Leg	1	

GST (If any) _____ %

Note: (i) If nothing is mentioned in GST field, rates quoted by you will be considered as inclusive of GST.

Authorized signatory of agency
with Rubber Stamp


 (M.G.Sonkamble)
 Executive Engineer
 EHV(O&M) Division Nanded