

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD
(CIN No. U40109MH2005SGC153646)

From The Chief Engineer (C&M), 5 th Floor, A-Wing, Prakashganga, C-19, "E" Block, Bandra – Kurla Complex, Bandra (East), Mumbai – 400 051. Tel: 022-2659 5125 (O)/022-2659 5124 (P) E-mail: cecm@mahatransco.in	To M/s Tesla Transformers (India) Ltd 23 “A” Sector b Industrial Aria, Govindpura, Bhopal (MP) India - 462023 Tel: +91 755 2586778, 2586328 Fax: +91-755-2581865 Email: projects@teslaindia.co , mktg@teslaindia.co
---	--

MSETCL/CO/C&M/PT/SS Pre-Tender/CAMP/MUM./01Date: 29/05/2020

Sub: Letter of Award for “Establishment of 132/33 KV Ner (Seoli) Ramnagar Sub-Station along with transmission line, Dist. Jalna” under Aurangabad Zone on turnkey basis against tender no. T-1955 (RFx No. 6000000772)”.

Ref: 1) SRM e -Tender No. T-1955/MSETCL/CO/C&M/PT/Pre-Tender (RFx No. 6000000772)
2) Your offer dtd. 30.10.2019 against subject tender.
3) Scheme B.R. No. 133/25 dtd. 22.02.2019
4) Tender acceptance 140/11 dtd. 08.01.2020
5) MERC approval –MERC/Capex/MSETCL/2017-18/2019-20/630 dtd. 22.08.2019

Dear Sir,

In connection with above subject, we are pleased to inform you that your above referred offer for the work of “ Establishment of 132/33 kV Ner (Seoli) Ramnagar Sub-Station along with transmission line, Dist. Jalna” under Aurangabad Zone on turnkey basis has been accepted. The details are as follows.

Description of works	Final Price quoted in Rs.	
Establishment of 132/33 kV Ner (Seoli) Ramnagar Sub-Station along with transmission line, Dist. Jalna” under Aurangabad Zone on turnkey basis for following scope of work:- 1. Construction of 132 kV DC line by making LILO on 132 kV Kanhaiyanagar - Partur line - 15 kms with following scope of work - i) 132 kV DC line on MC tower at proposed 132 kV Ner (Seoli) / Ramnagar s/s end -03 kms.	Supply : S/S-	Rs. 11,86,37,351.30
	Tr.Line-	Rs. 4,66,02,659.62
	ETC : S/S-	Rs 75,56,135.23
	Tr.Line-	Rs 1,59,48,631.41
	Civil : (SS)-	Rs. 7,31,61,116.52
	Total-	Rs.26,19,05,894.08
	(Inclusive of all Taxes & Duties) 3.31 % above tender estimate cost of Rs25,35,26,441.58	

ii) 132 kV DC line on DC tower between prop. 132 kV Ner/(Seoli)/Ramnagar s/s & LILO point -12 kms.. 2. 25 MVA, 132/33kV transformer with bays - 02 nos. 3. 132kV line bay - 02 nos. at proposed Ner (Seoli) 4. 33kV outlet - 04 nos. 5. 132 kV, 1X10 MVAR Capacitor bank - 01 no.	
--	--

(Rs. Twenty-Six Crore Nineteen Lakh Five Thousand Eight Hundred Ninety Four and Eight Paise Only)

The activity schedule for Supply, ETC & Civil works is enclosed herewith.

It may please be noted that the scope shall also include supply, ETC & Civil works of all equipments/materials, design of civil works and required materials which are not specifically listed in your offer but are necessary in order to meet the requirements of the substation as per tender specifications in all respect. Detailed terms and conditions will be as per the tender specifications, amendments thereof, your offer, clarifications thereon and contract agreement being executed shortly. The balance excess/extra material will not be accepted by MSETCL. Therefore the agency should take care for appropriate supply of material to complete the turnkey project. The work of above substation has to be completed within 12 months from the date of handing over of site (excluding monsoon i.e. 15/06 to 30/09) (Line + Substation).

You are requested:-

1. To intimate the acceptance of this LoA within 10 days from receipt of LoA.
2. To submit the bar chart indicating all activities for completion of the S/S within 10 days indicating all activities for completion of the project..
3. To submit price schedule with detailed break up of unit rate into ex-works price, tax, freight & insurance etc. within 10 days from receipt of LoA.
4. To complete the formalities like furnishing of Performance Bank guarantee as per the Clause No. 6.0 of Section-II of Book-I in prescribed format so that the contract agreement can be finalized.
5. **M/s Tesla Transformers (India)Ltd** shall submit the invoice as per GST regulations.

Thanking you.

Encl: Activity schedule.

Yours faithfully,

Chief Engineer (C&M)
(R.L. Gaikwad)

Copy s.w.rs. to:

1. The Director (Projects), MSETCL, Mumbai.

Copy f.w.cs. to:

1. The C.E., EHV PC O&M Zone, MSETCL, Aurangabad
2. The C.E., Project Scheme MSETCL, Mumbai
3. The C.E. (Design) MSETCL, Mumbai
4. The C.E. (Civil) MSETCL, Mumbai
5. The C.G.M. (F&A), MSETCL, Mumbai

Copy to:

1. The G.M. (F&A, Projects), MSETCL, Mumbai.
2. The S.E., EHV Projects Circle, MSETCL, Aurangabad
3. The S.E., EHV Civil CCM Circle, MSETCL, Aurangabad.
4. The S.E. (Post Tender), C.O. MSETCL, Mumbai.
5. The E.E., EHV Projects Division, Aurangabad.
6. The E.E., EHV Civil CCM Division, Aurangabad.
7. The E.E. (Design), C.O. MSETCL, Mumbai.
8. The E.E., PMT, MSETCL, Mumbai.For further needful
9. The E.E., FTU, MSETCL, Mumbai.For further needful

STANDARD ACTIVITY SCHEDULE FOR PAYMENT ELIGIBILITY				
Name of line: Construction of 132 kV DC line by making LILO on 132 kV Kanhaiyanagar – Partur line - 15 km				
COMPLETION PERIOD = 12 MONTHS				
Sr. No.	ACTIVITY	Schedule for completion of activities from date of LOA		Remarks/ Hold points for payments
		Commencement	Scheduled period of completion	
1	Submission of performance B.G. in lieu of S.D.		Within 10 days	
2	Visit to site , verification of scope of work, Establishment of site office and mobilisation of gang	After 5 days	Within 20 days	
3	Signing of contract agreement	After 10 days	Within 30 days	
4	Trial pits and inspection of route	After 7 days	Within 21 days	
5	Preliminary & Detailed Survey	After 15 days	Within 68 days	At the rate minimum 20 km per month
6	Check survey	After 10 days	Within 136 days	At the rate minimum 10 km per month
7	Approval of detailed /check survey & trial pits	After 20 days	Within 145 days	
8	Requisition of drawings of towers, stubs templates	After 5 days	Within 20 days	
9	Issuance of all drawings for execution by MSETCL	After 10 days	Within 30 days	Copy of trial pits report duly approved by Engineer in Charge be furnished
10	Collection of drawings by Contractor	5 days	15 days	
11	Preparation of shop drawings	15 days	45 days	
12	Proto manufacturing, assembly of tower, submission of call for inspection (if applicable)	After 30 days	Within 45 days	
13	Proto inspection	After 37 days	Within 60 days	
14	Supply of stub & stub setting templates	After 20 days	Within 160 days	Supply to be effected within 15 days after approval of check survey
15	Tower foundation	After 20 days	Within 250 days	At the rate minimum 10 locations per month
16	Supply of tower material	After 40 days	Within 270 days	The foundation should have been casted for tower under supply. The towers to be supplied on per tower basis within 15 days of casting of foundation.
17	Erection of tower	After 60 days	Within 390 days	50% tower foundations should be completed, Erection @ 30 loc. per month.
18	Supply of conductor, earthwire, insulators for accessories towers & conductor /groundwire & insulator Hardware .	After 180 days	Within 275 days	Contractor's confirmation about complete erection of towers of equivalent route length is ready for stringing
19	Stringing of line	After 190 days	Within 300 days	Atleast 50% of towers should have been erected. Progress @ 10KM/Month
20	Miscellaneous works (fixing of tower accessories,tree cutting etc.)	After 220 days	Within 310 days	
21	Inspection, testing & commissioning of line	After 275 days	Within 360 days	
Note:-				
1	Contractor may execute the erection works ahead of schedule dates. In such an event the schedule date for supply of respective materials stands preponed accordingly and such supplies will become eligible for payments.			
2	The contractor shall supply the material as per actual requirement only, based on the bill of quantities after check survey & duly approved by Engineer incharge No additional /surplus material shall be accepted except specifically requisitioned by Engineer-In-Charge.			
3	The contractor can supply the material prior to scheduled delivery period,however,the payment eligibility will be from the date as per approved schedule period subject to satisfying conditions of hold points.			

Activity Schedule for Supply of Material

Tender No.: T-1955/MSETCL/CO/C&M/PT/SS Pretender (RFxNo. 6000000772)
Name of Work: Establishment of 132/33 KV Ner (Seoli) Ramnagar Substation Dist: Jalna
Name of Contractor: M/s Tesla Transformers (India) Pvt. Ltd
Completion Period: 12 months from the date of handing over of site.

Sr.No.	Name of the material	Scheduled period for supply of material from the date of handing over of site	Hold point for payment
1	Soil investigation, Drawing submission i.e. layout, Erection Key Diagram, Gantry Structure, Equipment Structure, Earth mat Design, Cable Trench, Control Room & Foundation Drawing etc.	Submission within 30 days	
2	Gantry Materials	Commencement after 30 days & completion within 180 days.	Gantry material should be as per approved layout & site requirement and equivalent to gantry foundations casted.
3	Equipment Structures	Commencement after 30 days & completion within 180 days.	Equipment structures should be as per requirement worked out from approved layout and equivalent to respective equipment foundations casted.
4	Conductor, Insulators Hardwares etc.	Commencement after 90 days & completion within 240 days.	Completion of 100% gantry foundations & 50% gantry erection.
5	CTs, PTs, LA, Isolator, BPI, CC, WT, Clamp & Connectors, M.K.	Commencement after 120 days & completion within 300 days.	1. Completion of erection of 100% gantries with bus bar stringing. 2. Erection of respective equipment structure.
6	MS Flats, CI Pipes, Earthing Material, Yard Lighting, ACDB, Power & Control Cables, Cable Trays, Modular cable transit system, Inflatable Emergency Lightning System	Commencement after 180 days & completion within 320 days.	Material should be as per finalization of BoQ by Engineer in charge as per actual requirement based on approved drawing and erection of 100% gantries with bus bar stringing.
7	Capacitor Bank, Circuit Breakers, Power Transformer, ICT & Station Transformer	Commencement after 240 days & completion within 360 days	1. Completion of all equipment foundations & erection of it, 100% gantries with bus bar stringing and transformer plinth, completion of 100% cable trench with laying of cable trays. 2. Completion of unfinished main control room * and 100%

			BCR.
8	PLCC Equipments, HF Cable, PLCC Panels/DCDB, FOTE Panel etc.	Commencement after 240 days & completion within 360 days.	Completion of all bay equipments except circuit breaker, power transformer / ICT and complete finishing of PLCC room.
9	Control & Relay Panels, SCADA, Battery Sets, Battery Chargers& Fire Fighting Equipments.	Commencement after 240 days & completion within 360 days.	Completion of control room, bay control rooms & erection of respective bay equipments& laying of respective control cable.
	Note: 1. The contractor may supply the material prior to schedule delivery period. However, the payment eligibility will be as per hold points indicated above. 2. *Unfinished control room: Completion of slab, brick work & plastering. 3. It is mandatory for agency to take possession of site within 30 days from the date of issuance of LOA.		

Activity Schedule for Erection Work

Tender No.: T-1955/MSETCL/CO/C&M/PT/SS Pretender (RFx No. 6000000772)
Name of Work: Establishment of 132/33 KV Ner (Seoli) Ramnagar Substation Dist. Jalna
Name of Contractor: M/s Tesla Transformers (india) Pvt. Ltd
Completion Period: 12 months from the date of handing over of site.

Sr.No.	Activity	No.of days/months from the date of handing over of site		Hold point for payments	Remarks
		Commencement	Completion		
	ERECTION				
1	Mobilization of gang	Within 30 days			
2	Arrangement of work and power supply, tests etc.	Within 30 days			
3	Erection of gantry structures and stringing of bus bar	Within 75 days	Within 180 days.		
4	Equipment structures	Within 75 days	Within 180 days.		
5	CT, PT, LA, Isolator, & BPI	Within 120 days	Within 360 days.		
6	Earthing, layout of earth mat, cable laying, cable trenches & yard lighting	Within 180 days	Within 360days.		
7	PLCC equipments i.e. WT CC, DCDB, & PLC terminal	Within 220 days	Within 360days.		
8	Erection of capacitor bank, power transformer and stations transformer	Within 240 days	Within 360days		
9	Installation of C&R panels, battery & battery charger.	Within 240 days	Within 360 days.		
10	Pre commissioning trials/testing.	Within 300 days	Within 360days.		
11	Electrical installation.	Within 300 days	Within 360 days.		