



MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.  
(CIN NO. U40109MH20055GC153646)

**From,**  
**The Office of Chief Engineer (Projects),**  
5<sup>th</sup> Floor, A-Wing, Prakashganga,  
C-19, "E" Block, Bandra – Kurla Complex,  
Bandra (East), Mumbai – 400 051.  
Tel: 022-2659 5125 (O)/022-2659 5124 (P)  
E-mail: cecm@mahatransco.in

**To,**  
M/s. Renuka Trans Infra Inc., Nagpur in  
consortium with M/s. Hyderabad Power  
Installations Pvt. Ltd., Hyderabad  
Ms-33, Amarjyoty Palace,  
Dhantoli, Wardha Road,  
Nagpur - 440012  
E-mail: renukatransinfrainc@gmail.com

MSETCL/CO/Projects/Pre-tender/T-2472/

001678

Date: 28 FEB 2025

**Subject:** Award of Turnkey works contract of establishment of 220/33 kV Yenwa Substation, Tal. Katol, Dist. Nagpur along with associated line under Nagpur Zone against tender no. T-2472 (RFx No. 6000001252).

– **Letter of Award thereof.**

- Ref:** 1) SRM e-Tender No. T-2472/MSETCL/CO/Projects/Pre-Tender (RFx No. 6000001252).  
2) Your offer dated 28.10.2024 against subject tender.  
3) Tender acceptance B.R. No. 170/46 dtd. 17.01.2025.

Dear Sir,

In connection with the above subject, we are pleased to inform you that your offer for the turnkey works contract of establishment of 220/33 kV Yenwa Substation, Tal. Katol, Dist. Nagpur along with associated line under Nagpur Zone against tender no. T-2472 (RFx No. 6000001252) has been accepted for Supply, ETC & Civil portion as per details below -

Particulars of contract	Amount
Design, manufacture and supply of all materials execution of relevant civil works, erection, testing and commissioning of below works: 1) Installation of 2 x 50 MVA, 220/33 kV TF with HV/LV bays. 2) 2 x 220 kV line bays at proposed 220 kV Yenwa Substation. 3) 2 x 5.0 MVA, 33 kV Capacitor Bank at 220 kV Yenwa Substation. 4) 33 kV outlets - 08 nos. 5) Construction of 220 kV DC line by making LILO on 220 kV Kalmeshwar - Warud DCDC line at 220 kV proposed Yenwa Substation - 0.5 Km.	<b>Total</b> Rs. 48,06,01,009.32/- (Excl. of GST) (4.82% above the estimated cost of the tender of Rs. 45,85,01,249.07/-)

(Total cost is Rs. 56,71,09,191.00 i.e. 4.82% above the estimated cost of Rs. 54,10,31,473.90 including GST.)



The activity schedule with payment eligibility for turnkey construction of above work is enclosed herewith.

It may please be noted that the scope shall also include supply, ETC & Civil of all equipment/materials which are not specifically indicated in your offer but are necessary in order to meet the requirements of the work as per tender specifications in all respects.

Detailed terms and conditions will be as per the tender specification, amendments thereof, your offer, clarifications thereon and contract agreement being executed shortly. The above work has to be completed within **12 months (Excluding Monsoon)** from the date of handing over of site.

You are requested

- 1) To intimate the acceptance of this LOA within 10 days from the date of receipt along with the confirmation of Special Terms and Conditions as per tender, if any.
- 2) To submit Bar Chart within 10 days from the date of receipt of LOA, indicating all activities for completion of the project, to the S.E. EHV Projects Circle, Nagpur.
- 3) Submit price schedule with detailed breakup of unit rate into Ex-works Price, Freight & Insurance & Labour Cess, Tax etc. in uniform (single) percentage within 10 days from receipt of LOA.
- 4) To complete the formalities like furnishing of Performance Bank Guarantee in prescribed format enclosed in tender documents, within 30 days from the date of receipt of LOA so that the contract agreement can be finalized soon.
- 5) To submit, the 10% PBG to the value of Transformers/ ICTs shall be furnished by manufacturer/supplier for 5 years from date of supply.

Thanking you.

Encl: As Above

Yours faithfully,



**Sunil Suryawanshi**  
**Chief Engineer (Projects)**

**Copy s.w.r.to:**

- 1) The Chairman & Managing Director, MSETCL, Mumbai
- 2) The Director (Projects), MSETCL, Mumbai

**Copy f.w.cs.to:**

- 1) The C.E., EHV Projects cum O&M Zone, MSETCL, Nagpur
- 2) The C.E., Design/Civil/AC&I, MSETCL, Mumbai
- 3) The Chief General Manager (F&A), MSETCL, Mumbai

**Copy to:**

- 1) The G.M. (F&A-I), FTU Section MSETCL, Mumbai
- 2) The S.E., EHV Projects Circle, MSETCL, Nagpur
- 3) The S.E., EHV Civil CCM Circle, MSETCL, Nagpur

**Sub:** Award of Turnkey works contract of establishment of 220/33 kV Yenwa Substation, Tal. Katol, Dist. Nagpur along with associated line under Nagpur Zone against tender no. T-2472 (RFx No. 6000001252). – Letter of Award thereof.



**Tender No.:** T-2472/MSETCL/CO/Projects/Pre-Tender (RFx No. 6000001252)

**Name of Work:** Establishment of 220/33 kV Yenwa Substation, Tal. Katol, Dist. Nagpur along with associated line under Nagpur Zone.

**Name of Contractor:** M/s. Renuka Trans Infra Inc., Nagpur in consortium with M/s. Hyderabad Power Installations Pvt. Ltd., Hyderabad

**Completion Period:** 12 months from the date of handing over of site.

**Activity Schedule for Supply of Material**

Sr. No.	Name of the material	Scheduled period for supply of material from the date of handing over of site	Hold point for payment
1	Soil investigation, Drawing submission i.e. layout, Erection Key Diagram, Gantry Structure, Equipment Structure, Earth mat Design, Cable Trench, Control Room & Foundation Drawing etc.	Submission within 30 days	
2	Gantry Materials	Commencement after 30 days & completion within 120 days.	Gantry material should be as per approved layout & site requirement and equivalent to gantry foundations casted.
3	Equipment Structures	Commencement after 30 days & completion within 120 days.	Equipment structures should be as per requirement worked out from approved layout and equivalent to respective equipment foundations casted.
4	Conductor, Insulators Hardwares etc.	Commencement after 75 days & completion within 180 days.	Completion of 100% gantry foundations & 50% gantry erection.
5	CTs, PTs, LA, Isolator, BPI, CC, WT, Clamp & Connectors, M.K.	Commencement after 90 days & completion within 240 days.	1. Completion of erection of 100% gantries with bus bar stringing. 2. Erection of respective equipment structure.
6	MS Flats, CI Pipes, Earthing Material, Yard Lighting, ACDB, Power & Control Cables, Cable Trays	Commencement after 120 days & completion within 180 days.	Material should be as per finalization of BoQ by Engineer in charge as per actual requirement based on approved drawing and erection of 100% gantries with bus bar stringing.



7	Circuit Breakers, Capacitor Banks, Power Transformers & Station Transformer	Commencement after 230 days & completion within 270 days	1. Completion of all equipment foundations & erection of it, 100% gantries with bus bar stringing and transformer plinth, completion of 100% cable trench with laying of cable trays. 2. Completion of unfinished main control room * and 100% BCR. 3. <u>Submission of PBG for Transformer</u>
8	PLCC Equipments, HF Cable, PLCC Panels / DCDB, FOTE Panel etc.	Commencement after 200 days & completion within 230 days.	Completion of all bay equipments except circuit breaker, power transformer / ICT and complete finishing of PLCC room.
9	Control & Relay Panels, SCADA, ABT Meter, Battery Sets, Battery Chargers & Fire Fighting Equipments.	Commencement after 240 days & completion within 285 days.	Completion of control room, bay control rooms & erection of respective bay equipments & laying of respective control cable.
<b>Note:</b> 1. The contractor may supply the material prior to schedule delivery period. However, the payment eligibility will be as per hold points indicated above. 2. *Unfinished control room: Completion of slab, brick work & plastering. 3. It is mandatory for agency to take possession of site within 30 days from the date of issuance of LOA.			

### **Activity Schedule for Erection Work**

Sr. No.	Activity	No. of days/months from the date of handing over of site		Hold point for payments	Remarks
		Commencement	Completion		
	<b>ERECTION</b>				
1	Mobilization of gang	Within 30 days			
2	Arrangement of work and power supply, tests etc.	Within 30 days			
3	Erection of gantry structures and stringing of bus bar	Within 75 days	Within 180 days.		
4	Equipment structures	Within 75 days	Within 135 days.		
5	CT, PT, LA, Isolator, & BPI	Within 120 days	Within 270 days.		
6	Earthing, layout of earth mat, cable laying, cable trenches & yard lighting	Within 150 days	Within 210 days.		
7	PLCC equipments i.e. WT CC, DCDB, & PLC terminal	Within 210 days	Within 300 days.		
8	Erection of Circuit Breakers, Capacitor banks, power transformer and stations transformer	Within 240 days	Within 300 days		
9	Installation of C&R panels, ABT Meter, battery & battery charger.	Within 230 days	Within 310 days.		
10	Pre commissioning trials / testing.	Within 240 days	Within 330 days.		
11	Electrical installation.	Within 210 days	Within 340 days.		
Note: Please ignore the activity if not covered in scope of tender.					



### **Activity Schedule for Civil Work**

Sr. No.	Activity	No. of days/months from the date of handing over of site		Hold point for payments	Remarks
		Commencement	Completion		
(A)	CIVIL WORKS				
1	Visit to site, collection of site details. Layout, organizing soil investigation and submission of reports to Corporate Office and field office.	Within 10 days		The in charge S.E., to be contacted and joint visit to be undertaken with official nominated by him.	
2	Establishment of site store	Within 10 days	Within 30 days	Location to be got approved from Engineer in charge.	
3	Fencing, yard leveling	Within 15 days	Within 45 days	The scope of work and estimated cost to be got approved from S.E.(Civil) In charge of works	
4	Approach Roads, Rail track works	Within 45 days	Within 90 days		
5	Collection/finalization of foundation drawings & control room drawing	Within 30 days		Soil details within soil investigation report to be furnished with report of site visit duly certified by Engineer in charge of works (Addl.EE/EE).	
6	Civil foundation for:				
	Gantries	Within 30 days	Within 90 days		
	Equipments	Within 60 days	Within 120 days		
	Transformers	Within 30 days	Within 90 days		
	Capacitor Bank	Within 120 days	Within 150 days		
	End Bays	Within 60 days	Within 120 days		

7	Control Room				
	i)Foundations	Within 30 days	Within 90 days		
	ii)Brick work upto lintel	Within 90 days	Within 135 days		
	iii)Lintel to slab and casting of slab	Within 135 days	Within 180 days		
	iv)Plaster, trench with doors and windows	Within 210 days	Within 300 days		
	v)Painting finishing	Within 300 days	Within 330 days		
8	Construction of store shed & Cycle Stand	Within 270 days	Within 330 days		
9	Compound wall	Within 30 days	Within 210 days		
10	Metal spreading & GI Pipeline	Within 300 days	Within 330 days		
11	Watchmen Cabin/ Sump well	Within 300 days	Within 330 days		